	<del></del>									R	EVIS	SION	S					·							
LTR	Ų.						DES	CRIF	וסודי	١								DA	ΠE (YI	R-MO	-DA)	4	\PPF	ROVEI	)
																		ŀ				ı			
	•	•																							
															-										
																									-
i																					•				
																								•	
																									:
		· · · ·			_		γ		·	_	_			_	_	T					,		<del></del>	<del></del>	
REV					L			_																	
SHEET							L								L			L							
REV					_			_	L	L					<u> </u>			<u> </u>		_			_		Щ
SHEET	Щ				_	ļ		_		_	ļ						_			_					$\square$
REV STATUS OF SHEETS	┝	RE	*****			_			Ŀ	H	L						L							<u> </u>	-
		эn	EET	_	PRE	2	3 D BY	4	5	6	7	8	9 T	10	11			Ш	Ш		Ш			Ш	니
PMIC N/A				$\dashv$	Υ	אמ	<u>ໝໍ</u>	F	3. ł	لع	e.	ted			DEF	ENS							NTE	R	
STANDA	RDI	ZE	D		CHE	CKE	) BY						٦				DA	YTO	i, OH	Ю 4	5444				
MILIT	AR	Y		ļ		(a			on	nı	`_		┰	MIC	ROC	IRCU	IIT.	LIN	EAR	. 10	-BI	T AN	ALO	 G	
DRAV	VIN	G			APF	ROY	D B	Y 1)	1	ييل	2			TO	DIG	ITAL	. co	NVER	TER	MO	NOL.	THI	c s	ĪLIC	ИС
THIS DRAWING					DRA	WINC	APF	PROV	AL D	TE.	_		十	SIZE	Т	C	AGE (	ODE		Т					
FOR USE BY ALL	CIES C	)F TH	E	<b>"</b> [			LY 1							A				68		5	596	52-	88	35C	)5
DEPARTMENT	OF C	)EFE!	NSE	ſ	REV	ISION	LEV	EL					╊												-
AMSC N/A														S	HE	=T		1	(	OF		11			- 1

DESC FORM 193 SEP 87

 $\bullet$  u.s. government printing office: 1987 — 748-129/40911  $5962\!-\!E735$ 

1. SCOPE				
1.1 Scope. This drawing describes development 1.2.1 of MIL-STD-883, "Provisions for non-JAN devices".	vice requireme or the use of	nts for class   MIL-STD-883 in	B microcircu conjunction	uits in accordance with compliant
1.2 Part number. The complete part nu	umber shall be	as shown in t	he following	example:
Drawing number Device	type Case		X                   	er
(1.2.	.1) (1	•	MIL-M-38510	
1.2.1 <u>Device types</u> . The device types				follows:
Device type Generic numbe	<del></del>	Circuit fund		<u>.</u>
01 AD573 02 AD673				essor interface essor interface
1.2.2 <u>Case outline</u> . The case outline as follows:	shall be as d	esignated in ap	pendix C of	MIL-M-38510, and
Outline letter		Case outlin	<u>1e</u>	
R	D-8 (20 lead,	1.060" X .310"	' X .200"),	dual-in-line package
1.3 Absolute maximum ratings.				
$V_{CC}$ to digital common VEE to digital common Analog common to digital common Analog input to analog common Control inputs Digital outputs (high impedance st Storage temperature range Lead temperature (soldering 10 sec Power dissipation $(P_D)$ Thermal resistance $(\theta_{JC})$ Thermal resistance $(\theta_{JC})$	ate)		.5 V dc / dc V dc to VCC to YCC C to +150°C C	, appendix C
1.4 Recommended operating conditions.				•
VCC VEE	e (T <sub>A</sub> )		dc V dc C to +125°C	
STANDARDIZED	SIZE	,	T	
MILITARY DRAWING	A		596	2-88505
DEFENSE ELECTRONICS SUPPLY CENTER		REVISION LEV		SHEET
DAVTON ONIO 45444		1		

#### 2. APPLICABLE DOCUMENTS

2.1 Government specification and standard. Unless otherwise specified, the following specification and standard, of the issue listed in that issue of the Department of Defense Index of Specifications and Standards specified in the solicitation, form a part of this drawing to the extent specified herein.

SPECIFICATION

MILITARY

MIL-M-38510 - Microcircuits, General Specification for.

**STANDARD** 

MILITARY

MIL-STD-883 - Test Methods and Procedures for Microelectronics.

(Copies of the specification and standard required by manufacturers in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting activity.)

2.2 Order of precedence. In the event of a conflict between the text of this drawing and the references cited herein, the text of this drawing shall take precedence.

#### 3. REQUIREMENTS

- 3.1 Item requirements. The individual item requirements shall be in accordance with 1.2.1 of MIL-STD-883, "Provisions for the use of MIL-STD-883 in conjunction with compliant non-JAN devices" and as specified herein.
- 3.2 Design, construction, and physical dimensions. The design, construction, and physical dimensions shall be as specified in MIL-M-38510 and herein.
  - 3.2.1 Terminal connections. The terminal connections shall be as specified on figure 1.
  - 3.2.2 Case outline. The case outline shall be in accordance with 1.2.2 herein.
- 3.3 Electrical performance characteristics. Unless otherwise specified, the electrical performance characteristics are as specified in table I and apply over the full ambient operating temperature range.
- 3.4 Marking. Marking shall be in accordance with MIL-STD-883 (see 3.1 herein). The part shall be marked with the part number listed in 1.2 herein. In addition, the manufacturer's part number may also be marked as listed in 6.4 herein.

STANDARDIZED MILITARY DRAWING	SIZE A		5962	-88505	
DEFENSE ELECTRONICS SUPPLY CENTER DAYTON, OHIO 45444		REVISION LEVE	L	SHEET 3	

	TABL	£ I. Electrical	performance cha	racterist:	ics.			
Test	  Symbol		ions <u>1/</u> +125°C	Device types	  Group A  subgroups	l Lim	its	Unit
		unless otherw	rise specified		 	Min	Max	
Relative accuracy	I RA	Unipolar and   transactions	All	1 1	  195	+.195	l % of	
	1	transactions	-3 codes	01	2,3,12	098	+.098	FS
				02	2,3	195	+.195	
Differential	DNR	All codes tes		01	1	8		Bits
nonlinearity		unipolar and	Dipolar	01	2,3,12	10		
			·····	02	1,2,3	8		
Full-scale error	  Ae	!   Unipolar <u>3</u> / 		A11	1	  -40 	  +40 	mΥ
	i . ! !	Bipolar <u>3</u> /		ATT	1	-20	+20	
Full-scale temperature drift	ΔAe			01	2,3	488	+.488	% of FS
temperature drift	4			02	2,3	781	.781	гз
Offset error	vos	   First transit	ion	A11	1	-20	+20	mV
	1	 		01	12	-10	10	
Offset temperature		 		01	2,3	195	+.195	
drift	Δt			02	2,3	391	+.391	FS
Bipolar zero error	BPZE	Low side MSB t	ransaction	A11	1	-20	+20	mV .
		bipolar		01	12	-10	+10	
Bipolar zero	ΔΒρζΕ/	Low side MSB transaction bipolar		01	2,3	195	+.195	
temperature drift	Δt			02	2,3	391	+,391	FS
	IOLT	V <sub>OH</sub> = 5.0 V	DBO - DB9	01	1,2,3	-40	+40	μ <b>Α</b>
current	! 	V <sub>OL</sub> = 0.0 V	DBO - DB9	02	1,2,3	-40	+40	

See footnotes at end of table.

STANDARDIZED MILITARY DRAWING	SIZE A		5962-	5962-88505		
DEFENSE ELECTRONICS SUPPLY CENTER DAYTON, OHIO 45444		REVISION LEVEL	•	SHEET	4	

				Davidson	Curve	1 3 3	+-	Unit
Test	Symbol   	Cond   -55°C < TA   unless othe	itions 1/ < +125°C rwise specified	Device   types 	Group A  subgroups 	Limi Min	Max_	
Power supply rejection ratio	PSRR		15.75 V ≤ V <sub>EE</sub> ≤	A11 	1,2,3	-78.1	+78.1	mV
	     	V <sub>CC</sub> = 5.0 V, -	12.6 V < VEE <	01	12	-19.5	+19.5	
Power supply current	ICC	DATA READY 10 or DATA READY (during conve	ow Thigh ersion), T <sub>A</sub> = 25°C	A11	1		15	mΑ
•	IEE	TA = 25°C		   A11 	1	-15		
Input voltage (high)	I VIH		4/	A11 	1,2,3	   2.0   	! ! !	   <b>V</b> 
Input voltage (low)	V <sub>IL</sub>	-       		A11	1,2,3		0.8	
Input current (high)	I IH		4/	A11	1,2,3	-100	+100	μΑ
Input current (low)	IIL		4/	A11	1,2,3	-100	+100	   
Output voltage (low)	ν <sub>0</sub> μ	DATA READY, I <sub>OL</sub> = +3.2 m	DBO - DB9, A	01	1,2,3		0-4	   Y 
	1	DATA READY, I <sub>OL</sub> = +3.2 m	DBO - DB7, A	02	1,2,3	1	0.4	<u> </u> 
Output voltage	V <sub>OH</sub>	DBO - DB9, I	OH = -0.5 mA	01	1,2,3	2.4		T L
Output voltage (high)		DBO - DB7, I	OH = -0.5 mA	02	1,2,3	2.4		
Input resistance	RIN			All	4,5,6	3	7	KΩ
Conversion time	tc	See figure 2   T <sub>A</sub> = +25°C		A11	9	10	30	μS
Convert pulse width	t <sub>CS</sub>	T "		All	9	500		ns
See footnotes at en	d of tabl	e.			<del></del>			
STANDA			SIZE A		596	2-8850	5	
MILITARY DEFENSE ELECTR		PLY CENTER	RE	VISION LEV	/EL	SHI	ET	5

		Electrical performance character				<del></del> 7	,
Test			   Device   types	Group A	Limi	ts	Unit
	<u> </u>	unless otherwise specified	1		Min	Max	
DATA READY delay convert	tosc	See figure 2   T <sub>A</sub> = +25°C	All	9		1.5	μS
Data valid after HBE or LBE high	t <sub>HD</sub>		01	9	50	 	l l ns
Data valid after DATA ENABLE high	1	· ·     · ·       · ·       · ·       · ·         · ·           · ·           · ·           · ·             · ·	02		50   50		
Output float delay	tHL	   See figure 2   T <sub>A</sub> = +25°C	A11	9		200	    -
Data access time	top	T	A11	9	! !	250	

- $1/V_{CC}$  = +5 V,  $V_{EE}$  = -15 V, analog input through  $15\Omega$  resistor to pin 13, unipolar configuration. Unipolar configuration pin 16 (bipolar offset control) is grounded. Bipolar configuration pin 16 is not connected.
- Minimum resolution for which no missing codes are guaranteed: For 01 (10-Bit resolution device), 0.098% of full scale = 1 LSB. For 02 (8-Bit resolution device), 0.391% of full scale = 1 LSB.
- 3/ Device 01 full scale error guaranteed trimmable with a 200 $\Omega$  potentiometer. Device 02 full scale error guaranteed trimmable with a 50 $\Omega$  potentiometer.
- 4/ Conditions for device 01 are CONVERT, LBE, and HBE. Conditions for device 02 are CONVERT and DATA ENABLE.
- 5/ Guaranteed, if not tested.
- 3.5 Certificate of compliance. A certificate of compliance shall be required from a manufacturer in order to be listed as an approved source of supply in 6.4. The certificate of compliance submitted to DESC-ECS prior to listing as an approved source of supply shall state that the manufacturer's product meets the requirements of MIL-STD-883 (see 3.1 herein) and the requirements herein.
- 3.6 Certificate of conformance. A certificate of conformance as required in MIL-STD-883 (see 3.1 herein) shall be provided with each lot of microcircuits delivered to this drawing.
- 3.7 Notification of change. Notification of change to DESC-ECS shall be required in accordance with MIL-STD-883 (see 3.1 herein).
- 3.8 Verification and review. DESC, DESC's agent, and the acquiring activity retain the option to review the manufacturer's facility and applicable required documentation. Offshore documentation shall be made available onshore at the option of the reviewer.


STANDARDIZED MILITARY DRAWING	SIZE A			5962-	5962-88505		
DEFENSE ELECTRONICS SUPPLY CENTER DAYTON, OHIO 45444			REVISION LEVEL		SHEET	6	

	Terminal	symbol
Device	01	02
Case	i R	R
Terminal   number   1   2   3   4   5   6   7   8   9   10   11   12   13   14   15   16   17   18   19   20	I DBO LSB IDB1 IDB2 IDB3 IDB4 IDB5 IDB6 IDB7 IDB8 IDB9 MSB IVCC ICONVERT IVEE IANALOG IN IANALOG COMMON IBIPOLAR OFF IDIG COMMON IDATA READY I LBE I HBE	INC* INC* INC* INC* IDBO LSB IDB1 IDB2 IDB3 IDB4 IDB5 IDB6 IDB7 MSB IVCC ICONVERT IVEE IANALOG IN IANALOG COMMON IBIPOLAR OFF IDIG COMMON IDATA READY INC

\* Pins 1 and 2 are internally connected to test points and should be left floating.

FIGURE 1. <u>Terminal connections</u>.

STANDARDIZED MILITARY DRAWING	SIZE A		5962-88505				
DEFENSE ELECTRONICS SUPPLY CENTER DAYTON, OHIO 45444		REVISION LEVEL	SHEET 7				



- 4. QUALITY ASSURANCE PROVISIONS
- 4.1 Sampling and inspection. Sampling and inspection procedures shall be in accordance with section  $\overline{4}$  of MIL-M-38510 to the extent specified in MIL-STD-883 (see 3.1 herein).
- 4.2 Screening. Screening shall be in accordance with method 5004 of MIL-STD-883, and shall be conducted on all devices prior to quality conformance inspection. The following additional criteria shall apply:
  - a. Burn-in test, method 1015 of MIL-STD-883.
    - (1) Test condition B using the circuit submitted with the certificate of compliance (see 3.5 herein).
    - (2)  $T_{A^{-}} = +125^{\circ}C$ , minimum.
  - b. Interim and final electrical test parameters shall be as specified in table II herein, except interim electrical parameter tests prior to burn-in are optional at the discretion of the manufacturer.
  - c. Optional subgroup 12 is used for grading and part selection at 25°C, and is not included in PDA.
- 4.3 Quality conformance inspection. Quality conformance inspection shall be in accordance with method 5005 of MIL-STD-883 including groups A, B, C, and D inspections. The following additional criteria shall apply.
  - 4.3.1 Group A inspection.
    - a. Tests shall be as specified in table II herein.
    - b. Subgroups 7, 8, 10, and 11 in table I, method 5005 of MIL-STD-883 shall be omitted.
    - c. Optional subgroup 12 is used for grading and part selection at 25°C.
  - 4.3.2 Groups C and D inspections.
    - a. End-point electrical parameters shall be as specified in table II herein.
    - b. Steady-state life test conditions; method 1005 of MIL-STD-883:
      - (1) Test condition B using the circuit submitted with the certificate of compliance (see 3.5 herein).
      - (2)  $T_A = +125^{\circ}C$ , minimum.
      - (3) Test duration: 1,000 hours, except as permitted by method 1005 of MIL-STD-883.

STANDARDIZED MILITARY DRAWING	SIZE A		5962-	5962-88505			
DEFENSE ELECTRONICS SUPPLY CENTER DAYTON, OHIO 45444		REVISION LEVEL		SHEET	9		

## TABLE II. Electrical test requirements.

MIL-STD-883 test requirements	Subgroups   (per method     5005, table I)
  Interim electrical parameters   (method 5004)	   
Final electrical test parameters   (method 5004)	1*,2, 3, 4, 9,
Group A test requirements   (method 5005)	1, 2, 3, 4, 5, 6, 9, 12
Groups C and D end-point   electrical parameters   (method 5005)	_ 1

\* PDA applies to subgroup 1.

### 5. PACKAGING

5.1 Packaging requirements. The requirements for packaging shall be in accordance with MIL-M-38510.

## 6. NOTES

- 6.1 <u>Intended use</u>. Microcircuits conforming to this drawing are intended for use when military specifications do not exist and qualified military devices that will perform the required function are not available for OEM application. When a military specification exists and the product covered by this drawing has been qualified for listing on QPL-38510, the device specified herein will be inactivated and will not be used for new design. The QPL-38510 product shall be the preferred item for all applications.
- 6.2 Replaceability. Microcircuits covered by this drawing will replace the same generic device covered by a contractor-prepared specification or drawing.
- 6.3 Comments. Comments on this drawing should be directed to DESC-ECS, Dayton, Ohio 45444, or telephone 513-296-5375.

# STANDARDIZED MILITARY DRAWING

DEFENSE ELECTRONICS SUPPLY CENTER DAYTON, OHIO 45444

SIZE A		5962	-88505		
	REVISION LEVEL		SHEET	10	

6.4 Approved source of supply. An approved source of supply is listed herein. Additional sources will be added as they become available. The vendor listed herein has agreed to this drawing and a certificate of compliance (see 3.5 herein) has been submitted to DESC-ECS.

Military drawing part number	Yendor CAGE number	Vendor <u>1</u> /   similar part   number	
5962-8850501RX	51640	AD573SD/883	
5962-8850502RX	51640	AD673SD/883	

1/ Caution. Do not use this number for item acquisition. Items acquired to this number may not satisfy the performance requirements of this drawing.

**Vendor CAGE** number

51640

Vendor name and address

Analog Devices, Incorporated Semiconductor Division 804 Woburn Street Wilmington, MA 01887

**STANDARDIZED MILITARY DRAWING** 

**DEFENSE ELECTRONICS SUPPLY CENTER** DAYTON, OHIO 45444

SIZE Α

5962-88505

**REVISION LEVEL** 

SHEET 11